



Town of Frisco

Public Works Department

P.O. Box 4100 • Frisco, Colorado 80443

TOWN OF FRISCO REQUEST FOR PROPOSAL

The Town of Frisco is accepting proposals for Asphalt Mill and Overlay on: Belford Street (Peak One), Dam Road, N. 3rd Ave Main St to Galena St, N. 3rd Ave Galena Dead End, S. 3rd Ave Main St. to Granite St, N. 4th Ave Main St to Galena Alley, N. 4th Ave Galena Alley to Creekside Drive and S. 4th Ave Main St. to Granite St. All work will be done in 2023. A mandatory site visit will be held on November 8th 2022 at 10:00 AM at 1 Main Street Frisco, Co 80443. Questions will be due November 15th 2022 and answered November 22nd 2022.

All proposals are due no later than 11:00 AM December 6th, 2022.

All proposals shall be mailed or hand delivered to the Town of Frisco PO Box 4100, 102 School Road; Frisco, CO 80443 or emailed to landons@townoffrisco.com.

Scope of Work:

- Mobilization
- Traffic Control
- Removal of asphalt mat includes saw cuts
- Adjust Man hole cover
- Aggregate Base course (class 6)
- 2" asphalt mill
- 2" asphalt overlay
- Parking space striping
- Road striping of double yellow and white lines
- Handicap spaces painted
- Inlay and installation of 24" crosswalk thermoplastics
- Inlay and installation of 18" stop bar thermoplastics
- Inlay and installation of straight right, left turn and right turn thermoplastics
- Installation of EV charging thermoplastic symbol

Nothing herein shall require the Town of Frisco to accept any proposal, and the Town of Frisco reserves the right to reject any or all proposals. The proposals shall remain open and not withdrawn for a period of 45 (forty-five) days from the date designed for its due date.

Dam Road					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Asphalt removal 2" Mill	SF	120,430		
2	Asphalt 2" Overlay	TON	1,471.9		
3	18" Stop Bar	SF	81		
4	24" Crosswalk	SF	0		
5	Striping Yellow	LF	2,695		
6	Striping White	LF	550		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		
9	Thermoplastics- straight right	EA	2		
10	Thermoplastics- right turn	EA	2		
11	Thermoplastics- left turn	EA	4		

N. 3rd Ave Main St. to Galena St.					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Asphalt removal 2" Mill	SF	18,846		
2	Asphalt 2" Overlay	TON	230.54		
3	18" Stop Bar	SF	18		
4	24" Crosswalk	SF	100		
5	Striping Yellow	LF	0		
6	Striping White	LF	1,364		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	2		

N. 3rd Ave Galena Dead End					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Asphalt removal 2" Mill	SF	4,704		
2	Asphalt 2" Overlay	TON	57.49		
3	18" Stop Bar	SF	18		
4	24" Crosswalk	SF	0		
5	Striping Yellow	LF	0		
6	Striping White	LF	0		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		

S. 3rd Ave main St. to Granite					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Asphalt removal 2" Mill	SF	19,276		
2	Asphalt 2" Overlay	TON	235.62		
3	18" Stop Bar	SF	18		
4	24" Crosswalk	SF	100		
5	Striping Yellow	LF	0		
6	Striping White	LF	1,185		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	3		
11	EV charging space	Spots	1		

N. 4th Ave Main St. to Galena Alley					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Asphalt removal 2" Mill	SF	9,976		
2	Asphalt 2" Overlay	TON	121.92		
3	18" Stop Bar	SF	0		
4	24" Crosswalk	SF	100		
5	Striping Yellow	LF	0		
6	Striping White	LF	500		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		

N. 4th Ave Galena Alley to Creekside Drive					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Asphalt removal 2" Mill	SF	15,120		
2	Asphalt 2" Overlay	TON	184.8		
3	18" Stop Bar	SF	0		
4	24" Crosswalk	SF	0		
5	Striping Yellow	LF	0		
6	Striping White	LF	60		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		

School Road					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Asphalt removal 2" Mill	SF	26,494		
2	Asphalt 2" Overlay	TON	291.45		
3	18" Stop Bar	SF	36		
4	24" Crosswalk	SF	200		
5	Striping Yellow	LF	810		
6	Striping White	LF	155		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		
10	Thermoplastics- right turn	EA	2		
13	Thermoplastics- straight left	EA	2		

S. 4th Ave Main Street to Granite Street					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Asphalt removal 2" Mill	SF	17,211		
2	Asphalt 2" Overlay	TON	210.35		
3	18" Stop Bar	SF	18		
4	24" Crosswalk	SF	100		
5	Striping Yellow	LF	0		
6	Striping White	LF	718		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	1		

Belford Street					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Asphalt removal 2" Mill	SF	15,700		
2	Asphalt 2" Overlay	TON	191.88		
3	18" Stop Bar	SF	0		
4	24" Crosswalk	SF	36		
5	Striping Yellow	LF	0		
6	Striping White	LF			
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		

Totals:					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Asphalt removal 2" Mill	SF	222,953		
2	Asphalt 2" Overlay	TON	2,995.95		
3	18" Stop Bar	SF	189		
4	24" Crosswalk	SF	636		
5	Striping Yellow	LF	3,505		
6	Striping White	LF	4,322		
7	Adjustments of valve boxes and man holes	LS			
8	Handicap spots	Spots	6		
9	Thermoplastics- straights right	EA	2		
10	Thermoplastics- right turn	EA	4		
11	EV charging space	EA	1		
13	Thermoplastics- straight left	EA	2		
14	Mobilization	LS	1		
15	Traffic Control	LS	1		