

# Building on Higher Ground

7006 S ALTON WAY, BLDG. E, SUITE 100 CENTENNIAL, CO 80112

TEL: (303) 221-7770 FAX: (303) 221-7774

# PROJECT GMP ESTIMATE - Draft / Preliminary

то: Slopeside Hall and Day Lodge

605 Recreation Way Frisco, CO 80443 ATTN: Town of Frisco DATE: 1/4/23

22138

JOB NO:

PROJ: Slopeside Hall and Day Lodge

Adr: 605 Recreation Way Frisco, CO 80443

A. D. Miller Services, Inc. is pleased to present to you the following budget pricing based on the following: Construction Documents dated 6/9/2022 and Specifications dated 6/9/2022

Div#	Division Description	Amount
01	General Conditions	\$ 489,713.73
02	Existing Conditions	114,417.00
03	Concrete	666,415.67
04	Masonry	148,407.00
05	Steel	221,665.00
06	Carpentry (Includes Exterior Stage)	1,225,811.98
07	Thermal & Moisture Protection	443,726.75
08	Openings - Doors & Windows	525,137.96
09	Finishes	361,997.74
10	Specialties	91,259.00
11	Equipment	27,052.50
12	Furniture	11,326.00
13	Special Construction (Solar System and Yurts)	164,960.64
14	Conveyance Equipment	233,090.00
21	Fire Suppression	136,150.00
22	Plumbing	299,265.73

Div#	Division Description	Amount
23	HVAC	566,446.44
26	Electrical	693,932.90
27	Communications	-
28	Electronic Safety & Security	35,500.00
31	Earthwork	282,261.00
32	Exterior Improvements	256,398.12
33	Utilities	254,240.00
	SUBTOTAL:	7,231,308.44
	Building Permit & Fees (By Owner)	-
	Insurance & Builders Risk	104,853.97

A.D. Miller OH&P		289,252.34
Performance and Payment Bond Fee	76,254.15	
<b>Estimating Contingency</b>	228,762.44	
Construction Contingency	266,889.52	571,906.11

#### **TOTAL CONSTRUCTION COST Including Contingency:**

\$ 8,197,320.86

#### Cost Breakouts:

1) Slopeside Hall	\$	6,192,988.93
2) Plaza	\$	1,151,686.92
3) Daylodge	\$	706,542.77
4) Tube Storage	\$	128,417.30
5) Yurt Relocation	\$	17,684.94
	Total \$	8,197,320.86

#### CLARIFICATIONS:

- 1) Cost based on Contract AIA A133 and A201 General Conditions.
- 2) Bid assumes the project will be completed sequentially in a single mobilization.
- 3) Bid does not include weather conditions.
- 4) Proposal includes Worker Comp, Liability Insurance, Builders Risk, and Performance Bond.
- 5) Allowances as specified and noted in the schedule of values documents.
- 6) All municipal, utility company and tap fees, permit and use tax, if applicable, are the responsibility of the owner. ADM to assist in permitting process. Coordination of all Construction Permit requirements.
- 7) The cost of third party engineering, inspections and testing are the responsibility of the owner. Comcast, Century Link and Xcel (Gas/Electric) connection costs by Owner. ADM to process paperwork and coordinate.
- 8) Excludes any and all abatement or environmental.
- 9) Bid excludes hard rock excavation and dewatering. Should AD Miller encounter hard rock or water during earthwork additional costs to be negotiated through change order process. Excludes soil/subsurface abatement and pest removal. Pending receipt of updated GeoTech report.
- 10) Assumes standard Grey concrete with industry best practices.
- 11) Masonry Stone and block: Standard size and color.
- 12) Proposal assumes structural steel to be shop prime painted.

Div # Division Description Amount

13) Estimate has been based upon current market pricing and historical data. Due to market volatility material is subject to increases without notice. The cost will be reviewed upon receipt of issued addenda/revision of plans for adjustment. AD Miller will do its best to maintain cost control, however should a material cost increase be implemented the delta will be handled through change order process.

- 14) Proposal includes an allowance for Sealants and caulking to include: dissimilar materials, site caulking and joints, and firestopping. Fireproofing has not been included as none has been specified.
- 15) Glazing assumed to be standard color with no FR glass / and industry standard STC rating.
- 16) Drywall scope assumes to be Level 4 finish at all visible locations.
- 17) Bid Excludes All FF&E (Equipment /Furnishings/ Cubbies), Signage, Audio / Video hardware and equipment. Includes rough in of locations as shown on plans.
- 18) Fire suppression designed and installed in accordance to NFP # 13 system. Excludes Dry System. (Excludes Exterior Buildings, Tube Shed, Yurt, etc.,)
- 19) Proposal includes a CPVC/PEX system with PVC underground, waste and drains.
- 20) All Low volt/ security/ Access control/ Data and structural cabling and equipment to be furnished and installed by owner
- 21) Excludes any work associated with Radio Amplification System and/or testing (if required), AES Radio Transmitter.
- 22) Proposal includes Fire Alarm and Fire Suppression System in Building Finished area. Design/Build and permitting by Contractor. (Excludes Exterior Buildings, Tube Shed, Yurt, etc.,)
- 23) Please note: Proposal assumes on site soil is suitable for structural fill.
- 24) This proposal is subject to change based on unknown items that may occur as result of COVID-19 such as material delays, labor shortages, jobsite disruptions or governmental intervention. Manufacturers and production facilities are feeling the impacts of decreasing international imports, health and safety concerns and economic impacts to their businesses. As a result, manufacturing production may be impacted. Therefore, lead times and production may be extended without warning and pricing may be affected. Known projects with critical completion schedules should be coordinated between parties.

### **Estimate Qualifications**

Slopeside Hall and Day Lodge Projects at the Frisco Peninsula Recreation Area

Owner: Town of Frisco

**Drawings:** Construction Documents and Specifications Dated 06/09/2022

**Phase: Sequence of Construction** 

### 00 - Procurement and Contracting Requirements

**Qualifications Based Information** 

Information Available to the Contractors

### 01 - General Requirements

- Summary

New Construction of 7835 SF, Recreation Hall/ Facility, Renovation of Day lodge Kitchen and entry to provide new Elevator, Site Improvements of Plaza Area, Relocation of Yurt and New construction of Tube Storage, located in Town of Frisco, CO. Anticipating Q2 - of 2023 start with completion Q2 2024. Wood construction, Stone, Cementitious siding and Metal Panel Exterior, with Asphalt shingle roof. Includes landscaping of Plaza area, sitework and utilities

- Unit Prices

Provided upon request.

- Substitution Procedures

To be allowed upon approval of Architect and Town of Frisco representatives.

- Contract Modifications Procedures

To be defined.

- Payment Procedures

To be defined.

- Project Management and Coordination

Utilization of AD Miller Procore Platform

- Construction Progress Documentation

Utilization of AD Miller Procore Platform

- Submittal Procedures

Utilization of AD Miller Procore Platform

- Quality Requirements

Standard Means and Methods, general construction practices.

- Temporary Facilities & Controls

Per industry standards.

Product Requirements
 Good / new quality.

- Execution

Standard Means and Methods, general construction practices. Preliminary schedule has been provided and will undertake every effort to maintain integrity, however due to market conditions and unforeseen conditions / events liquidated damages have been excluded.

- Closeout Procedures

To be defined.

- Operation and Maintenance Data

To be defined.

- Project Record Documents

Utilization of AD Miller Procore Platform

- Demonstration and Training

Per industry standards.

### 02 - Existing Conditions

022100 - Surveys

As Noted.

020500 - Tree Relocation, Protection and Trimming

Not included.

024100 - Demolition & Abatement

Minimal site demolition, abatement has been excluded. Dewatering has been excluded. Excavation and removal of hazardous/ organic material (if discovered) has been excluded and shall be handled via change order process.

### 03 - Concrete

032000 - Concrete Reinforcing

Class D Concrete with Fibermesh. All concrete work ha been estimated according to specified plans. Changes in wall (elevations) requiring additional forming will be billed in accordance. All Flatwork concrete estimated utilizing 4000 PSI strength.

033000 - Cast in Place Concrete

N/A - Not

033500 - Concrete Finishing

Standard Grey, Broom swept finish, excludes sealants

033713 - Shotcrete

Not included.

034000 - Precast Concrete

Not included.

034700 - Site Cast Concrete

Not included.

035400 - Gypcrete

Not included.

#### 04 - Masonry

042613 - Masonry Veneer

Cultured Stone Country Ledgestone (or equivalent)

042000 - Reinforced Unit Masonry

Trash enclosure-standard block, substructure. Elevator Core Standard Grey Lightweight smooth block, standard grey mortar

#### 05 - Steel

051200 - Structural Steel

Fabricated per AISC code Standards, installed / welded per industry standard does not include AISC certification.

051400 - Architectural Structural Steel Framing

Not included

054000 - Cold Formed Metal Framing

Not included.

055000 - Metal Fabrications

Includes bollards (6) locations, at entry, trash enclosure . Included trash enclosure gates

055100 - Metal Stairs

22 Treads as shown on A403

055913 - Metal Trellis

Recs Plus structure

057300 - Metal Handrails and Railings

Railing for Pan Tread stairs, 15' Mesh railing.

### 06 - Carpentry

061000 - Rough Carpentry

Wood construction, glu lam -(Excludes timber trusses), T&G Soffitted Areas, AD Miller to design / build Tube Storage structure utilizing 2x construction ILO or Forever Redwood Prefabricated Trusses. Excludes specialty wood timber construction

061719 - Cross Laminated Timber Panels

Not included

061753 - Wood Trusses

Included in Section 061000 Rough Carpentry

068316 - Fiber Glass Reinforced (FRP) Panels

Crane composites Glassboard Class C Pebbled & Designs Smooth per plans

062000 - Finish Carpentry

Includes Tongue and groove ceiling where specified, interior countertops, cabinets and architectural woodwork per plans and specifications unless notec otherwise. Please note PL-2 Burnished Chestnut "Natural Grain" assume Horizontal Stard grain laminate at -60 Matte is acceptable. Interiors of cabinets with doors to be White Melamine. Wood species to be Plain Maple

#### 07 - Thermal and Moisture Protection

071000 - Bituminous Waterproofing

**WR Meadows Sealmastic** 

071300 - Sheet Waterproofing

Not included

071400 - Fluid-Applied Waterproofing

Not included

071800 - Traffic Coatings

Not included

071900 - Water & Graffiti Repellants

Not included

072100 - Thermal Insulation

Perimeter foundation 2" (R10) 25 PSI Rigid Insulation. Bid includes unfaced in the ceilings due to the 6" polyiso on roof deck, to prevent moisture trap. Sound ce

072119 - Foamed In Place Insulation

Foam windows & doors Exterior wall detailing / air sealing only.

072400 - Exterior Insulation & Finish System (Stucco)

Not included

072500 - Weather Barriers

As Noted.

074213 - Metal Wall Panels

28" x 28" square spline joint rainscreen ACM panel attaching directly to Minimum 5/8" plywood substrate.

074646 - Fiber Cement Siding & Wood Siding

Cement fiber board.

075400 - Roofing

Includes 6.5 nail base on Slopeside deck, with CertainTeed Landmark Pro asphalt shingle roof system. and EPDM on South Side

076200 - Sheet Metal Flashing and Trim

Galvanized, sheet metal flashing and trim.

077200 - Roof Accessories

6" Box Pre-finished gutter

077600 - Paver Systems

Not included.

078100 - Applied Fireproofing

Not included.

078400 - Fire Stopping

Assumed code minimum.

079200 - Joint Sealants

Allowance

079500 - Expansion Joints

Allowance

#### 08 - Doors and Windows

081113 - Hollow Metal Doors

HM Doors and frames manufactured by Curries

081400 - WD Doors

Wood doors manufactured by Marshfield, plain sliced white maple with heavy duty particle core construction. Stile and rail wood doors are Karona, knotty Alder with heavy particle core construction.

083300 - Overhead Coiling Doors & Smoke Barriers

Raynor Fire Curtain Series UCP type N-10, and OH doors per specification

084000 - Aluminum-Framed Storefronts

Exterior - Install Tubelite T14000 I/O thermal storefront with glazing plane, standard anodized finish, solorban 60

Interior Tubelite E4500 series, standard anodized finish, 1/4" tempered. FB-03 has been excluded as not identified on plan set. (Please note leadtime 20-22 to include hardware)

085000 - Vinyl Windows & Sliding Doors

N/A - VE Alternate to be provided

087000 - Door Hardware

Per Plans and specifications

088000 - Glazing

Included in Division 084000 Aluminum-Framed Storefront

089000 - Louvers and Vents

Allowance

#### 09 - Finishes

092116 - Gypsum Board Assemblies

Assumed 5/8" drywall with Level 4 finish

093000 - Tiling

Per specification

095100 - Acoustical Ceilings

As noted.

096400 - Hardwood Flooring

N/A - Not included

096500 - Resilient Flooring

Per specification

096800 - Carpeting

Per specification

099100 - Painting

Per Plans / Specifications

099663 - Painted Pavement Markings

As Noted.

### 10 - Specialties

101400 - Signage, House Numbers, and Building

Allowance - Code Based signage only

102200 - Chain Link Fencing

N/A - Excluded

102800 - Toilet, Bath, and Laundry Specialties

Per plans and specifications

103000 - Fireplaces and Stoves

N/A - Excluded

104400 - Fire Protection Specialties

Code minimum

105000 - Storage Specialties

(7) Olympus - 4 -Tier Metal lockers

105500 - Specialties Walls

(2) Moderco 841 Series manually operated folding panel partitions

### 11 - Equipment

116000 - Entertainment & Recreation Equipment

By owner

113013 - Appliances

Allowance pending detail

118000 - Facility Maintenance and Operation Equipment

Not included

111000 - Vehicle and Pedestrian Equipment

Not included

#### 12 - Furnishings

122000 - Window Treatments

Lutek single manual roller shade with fascia

123600 - Countertops

Included in Architectural millwork

123000 - Cabinets (casework)

Included in Architectural millwork

### 13 - Special Construction

131100 - Solar

Included

133400 - Fabricated Engineered Structures

See steel structure for Trellis (manufactured by Recreation Plus)

# 14 - Conveying Equipment

142000 - Elevators

Included TK elevators - Please note engineer/ architect to verify Shaft clearance dimensions as specified unit does not fit within clearance

149100 - Lifts

Ski Chair Lifts as specified

### 21 - Fire Suppression

210000 - Fire Protection

Assume design build - allowance

# 22 - Plumbing

220000 - Underground Plumbing

Estimate assumes a CPVC / PEX System with PVC underground, waste and drains.

221011 - Mains

Estimate assumes a CPVC / PEX System with PVC underground, waste and drains.

221000 - Rough In

As Noted.

224000 - Plumbing Fixtures

Per Plans and specifications

221022 - Gas - Above Slab

Per Plans and Specifications

223400 - Plumbing Equipment

As Noted.

### 23 - Heating, Ventilating and Air Conditioning

230000 - HVAC Equipment

Per Plans and Specifications

233100 - Ductwork

As Noted.

233300 - Duct Connectors/Connections

As Noted.

233713 - Grilles/Registers/Louvers

As Noted.

233313 - Dampers

As Noted.

233300 - Install Materials

As Noted.

### 25 - Integrated Automation

250000 - Integrated Automation

Not included.

### 26 - Electrical Systems

260533 - Electrical Scope

Per Plans and specifications. Please note assume electrical allowance of 3500 for Elevator electrical. To be reviewed upon confirmation of electrical plans and elevator specification acceptance. Excludes Lightning protection.

261150 - Wire and Cables

As Noted.

260534 - Switches and Receptacles

As Noted.

265000 - Interior Light Fixture

Assume allowance - fixture TBD

262400 - Panel

As Noted.

271000 - TV Outlet

As Noted.

284600 - Fire System

As Noted.

263213 - Generators

Not included.

#### 27 - Communications

271000 - Structured Cabling

Structured cabling has been excluded, to be provided by owner. Includes Rough in only.

273000 - Area of Refuge Communication System

Not included / indicated on plans. Excluded

### 28 - Electronic Safety and Security

280533 - Radio Amplification System

Not included

281000 - Access Control

Not included

284000 - Fire Alarm System (Contractor Design)

Assumed design build to include: design, materials, installation, smoke detectors, voice evacuation FA panel, pull stations, sprinkler monitors, strobes, duct dete

#### 31 - Earthwork

310000 - Earthwork

Estimate has been based upon a single mobilization, to include grading, excavation, backfill. Excludes Dewatering, hard rock excavation, haul off of organic/hazardous/ contaminated materials. Assumes ability to stock pile and to disperse spoils across site.

312500 - Erosion and Sedimentation Controls

As Noted.

314000 - Shoring and Underpinning

Not included

316000 - Special Foundations and Load-bearing Elements

### 32 - Exterior Improvements

321216 - Asphalt Paving

As Noted.

321300 - Site Concrete

As Noted.

321800 - Athletic and Recreational Surfacing

Not included

323300 - Site Furnishings

Included in landscaping

323100 - Decorative Fences and Gates

N/A - Not included

329000 - Planting and Landscaping

Per Plans and specifications

#### 33 - Utilities

331000 - Water Utilities

Per Plans and specifications

333000 - Sanitary Sewerage Utilities

Per Plans and specifications

334000 - Storm Drainage Utilities

Per Plans and specifications

334100 - Perimeter Drainage

Assume wrapped perforated drainage pipe where shown

335000 - Gas Utilities

Not included - To be coordinated with Town of Frisco and Utility provider

337000 - Electrical Utilities

Not included - To be coordinated with Town of Frisco and Utility provider



Procession of the County Of		Hall and Day Lodge				Project S.F.	10.720			P/SF:(Inc Alts)			
	Adr: 605 Recre	eation Way					Slopeside Hall and Day 1	Lodge		Total + alts:			
Omitric   List   State   Control   List   Control   Co		PRELIMINARY BUDGET - SC	HEDULE OF	'VALUES			Frisco, CO 80443  2,414			Total:			
State   Colored   Colore	Descr	iption	Quantity	Unit		Total	Division Total	Breakout 1 Slopeside Hall	Breakout 2 Plaza	Breakout 3 Day Lodge	Breakout 4 Tube Storage	Breakout 5 Yurt Relocation	Notes
Figure   Color   Col	01 GENERAL CONDITION	General Condition		LS	489,713.73	489,713.73		391,770.98	97,942.75				
Figure   Color   1   15   15   15   15   15   15   15							489,713.73	391,770.98	97,942.75				
State Committee (C-2010)   1   15   15   15   15   15   15   15	02 EXISTING CONDITION	Existing	0.00	ST ST	- 43,350.00 32,250.00	28,900.00 21,500.00		28,900.00		21,500.00			3rd Party Testing By Owner Survey
		Selective Demolition 02-41 Site Cleaning 02-50	13 1	TS	23,362.50	53,417.00		4,800.00	41,910.00	11,507.00		1 1	Misc Dono Excluded Abatement & Environmental
State   County   Co							114,417.00	33,700.00	41,910.00	38,807.00			
Prezent   14-000   1   15   15   15   15   15   15		Concrete Complete 03-00 Concrete Pumping 03-30 Concrete Washouts 03-53 Concrete Cutting and Bering 03-80	0 00 00	1.5 1.5 1.5 1.5 1.5	564,633.00 8,700.00 11,700.00 6,375.00	648,565.67 5,800.00 7,800.00 4,250.00		212,102.51	354,572.63 5,800.00 7,800.00	17,483.55	64,406.98		Concrete Complete
Prezint   1-15							666,415.67	216,352.51	368,172.63	17,483.55	64,406.98		
Nictial DIV 6  CCT	04 MASONRY	Precast 04-00 Stone Assemblies 04-40 Manufactured Masonry 04-70	00 00	ST TS TS	45,000.00 56,137.50	20,974.00 65,942.00 61,491.00		20,974,00 65,942.00 61,491.00					Includes Trash Enchause and Elevator Core
Netal   05-000   1   LS   170,131.51   221,665.00   96,690.00   112,975.00   12,000.00							148 407 00	148 407 00	,				
Subrotal DIV Sc   CCT   LS   LOTS,297.50   R38,346.36   R38,346.36   R38,346.36   R38,346.36   R38,346.36   R38,346.36   R38,346.36   R39,376.36   R30,376.36	05 STRUCTURAL STEEL	Metals 05-00	00	TS	170, 131.51	221,665.00	Or Carlon	96,690.00	112,975.00	12,000.00	,		Includes Architectural and Structural Steel, Shop Prime Painted
cough Carpentry         6-1000         1         LS         1,078,297,50         838,346.38         712,594,93         -         1,25,752.05         -							221,665.00	00.069,96	112,975.00	12,000.00			
Subtoral DIV 06   CCT   LS   S7.3465.01   LS	06 CARPENTRY	Rough Carpentry 06-10		rs	1,078,297.50	838,346.98		712,594.93		125,752.05	•		Irusses (penang shops), Praming, Joist, Subjioor, Exterior Sheathing, Roof Sheathing, Backing and Blocking, en. Excludes Timber constrution. See qualifications Interior Millswork - Cathinese, cubbies, kitchen and office.
Subtoral DIV 06         CCT         1,225.811.38         1,002,164,93         -         133,67755         -         -           Evaluer proofing of cental Protection (7-200)         1         L.S         43,800,00         20,999,00         20,999,00         -		Architectural Woodwork 06-40	1 1	LS	266,107.50	387,465.00		379,570.00	,	7,895.00	1		Counter Tops - Plam., Solid surfaces.
Exhibitor of DI VI Corp.         1. LS         57,446.51         24,432.60         20,872.50         -         3,560.00         -		Subtotal DIV 06					1,225,811.98	1,092,164.93		133,647.05			
1   LS   33,000   22,000,00   22,000,00	07 THERMAL AND MOIST	PROTECT  Damp & Waterproofing 07-10  Thermal Protection 07-20	00 1	LS	57,346.51 43,800.00	24,432.50		20,872.50 20,999.00	1 1	3,560.00			Below Grade Foundation Damp proofing Interior Thermal Insulation & Sound Batt
1   LS		Stucco & EIFS 07-24.	20	r.	- 00 00	- 000 000		- 000000					Excluded None Shown
1         LS         12,009.38         9,706.25         -		Roofing & Siding Panels   07-400	2 2	S. F.	33,000.00	349,455.00		327,143.00	5,227.00		17,085.00		Exterior System Asphalt Shingle and Membrane Roof
CGT 443.726.75 449.404.75 9.227.00 6.810.00 17.085.00	Sealants & Cauli	Flashing & Sheet Metal 07-60 king - Caulking and Firestop 07-92	13 1	LS	12,009.38	9,706.25		9,706.25	4,000.00	3,250.00	1 1	1,200.00	
00000000 0000000 000000000000000000000		Subtotal DIV 07					443,726.75	409,404.75	9,227.00	6,810.00	17,085.00	1,200.00	

	Unit	Unit	Unit Price	Good Faith Estimate	Total	Division Total	Breakout 1 Slopeside Hall	Breakout 2 Plaza	Breakout 3 Day Lodge	Breakout 4 Tube Storage	Breakout 5 Yurt Relocation	Notes
				146,775.00 21,112.50 22,500.00	70,072.96 16,175.00 14,690.00		70,072.96 12,667.50 14,690.00		1,407.50	00:006	1,200.00	Installation
				41,970.00 9,750.00 11,250.00	411,200.00 6,500.00 6,500.00		411,200.00 6,500.00 6,500.00					2 Openers - Allowance Allowance - Misc.
	_	_				525,137.96	521,630.46		1,407.50	00'006	1,200.00	
				198,330.00	115,000.00 21,750.00		106,300.00		8,700.00			Interior Deywall and Finish ACT Ceilings
				26,175.00 26,175.00 58,414.13	141,804.99 24,500.00 58,942.75		85,394.91 24,500.00 47,154.20		26,410.08 - 11,788.55			Allowance
						361,997.74	285,099.11		76,898.63			
				, 6			,	•	,	1		Excluded - By Owner
6,75	6,75	6,75	6,75	6,750.00	10,524.00		4,503.22 10,524.00					Allowance - Code Based Signage
4,725.00	4,725	19,772	4,72:	5.00	3,150.00		3,150.00					Excluded - By Owner
1,632,00 26,250,00 1,875,00	1,632.0 26,250.1 1,875.1	1,632.0 26,250.1 1,875.1	1,632.0 26,250.0 1,875.0	2 2 2	1,088.00 53,739.00 8,750.00		1,088.00 53,739.00 8,750.00					АПонапсе
						91.259.00	91 262 22			٠		
1,875.00	1,875.0	1,875.0	1,875.0	0	1,250,00	OLY CORK	1,250.00		- 10,597.00			Supplied By Owner - allowance for installation only Allowance
						27,052.50	16,455.50		10,597.00			
,	•	•	,		,			,	1		1	Exchided
16,500.00	16,500.00	16,500.00	16,500.00		11,326.00		11,326.00				1 1	Excluded
	,	,			1				,	,		Excluded
						11,326.00	11,326.00					
150,000.00	150,000.00	150,000.00	150,000.00		154,960.64		154,960.64				10,000.00	
						164,960.64	154,960.64		-		10,000.00	
285,000.00	285,000.00	285,000.00	285,000.00	_	225,000.00 8,090.00		112,500.00 8,090.00		112,500.00			New Elevators
_						233,090.00	120,590.00		112,500.00			
97,5	97,5	97,5	97,5	97,500.00	136,150.00		105,000.00	•	31,150.00	,	1	Dry System Excluded
_				Ī		136.150.00	105,000.00		31,150.00			

22 PLUMBING			,			Good Faith Estimate	Total	Division Total	Slopeside Hall	Plaza	Day Lodge	Tube Storage	Yurt Relocation	Notes
_	Plumbing 22-0000	2-0000	-	TS		352,350.00	299,265.73		224,449.30		74,816.43	1		
	Subtotal DIV 22	ССТ						299,265.73	224,449.30		74,816.43			
23 HVAC	HVAC 23-0000	3-0000	-			537,414.28	566,446.44		531,447.00	1	35,000.00	,	•	
	Subtotal OTHER 23							566,446.44	531,447.00	-	35,000.00			
26 ELECTRICAL	Electrical 26-0000	0000-92	-	TS		386,250.00	693,932.90		617,666.39		62,173.65	10,892.00	3,200.86	
	Subtotal DIV 26	CCT						693,932.90	617,666.39		62,173.65	10,892.00	3,200.86	
27 COMMUNICATIONS	Communications 27-0000 Structured Cabling 27-1000	27-0000		LS		1.1	1 1							Excluded by Owner - Rough in only Excluded by Owner - Rough in only
	ubtotal DIV 27	ССТ												
28 ELECTRONIC SAFETY & SECURITY Elec Access Cutrl & In	AFETY & SECURITY Elec Access Cutrl & Intrusion Detec. 28-1000 Fire Detection 28-3100	28-1000		LS LS		75,682.50	35,500.00		25,560.00		9,940.00		, ,	Excluded - By Owner- Includes Rough In only
	Subtotal DIV 28	CCT						35,500.00	25,560.00		9,940.00			
31 EARTHWORK	60	11-0000	1	TS		128,265.00	235,261.00		80,000.00	135,261.00	,	20,000.00	,	Includes excavation
3	Shoring & Underning 31-2319	31-2319		rs			- 00 000 00		- 00 000 00					Excluded
	Erosion Control 31-8000	31-8000		rs		19,098.00	27,000.00		15,000.00	12,000.00		,		лиоминсе
	Subtotal DIV 31	CCT						282,261.00	115,000.00	147,261.00	-	20,000.00		
32 EXTERIOR IMPROVEMENTS														
Land	Asphalt & Paving 32-1000 Landscaping and Irrigation 32-1001	32-1000 12-1001		LS		108,055.50	31,651.00 203,327.12		1 1	31,651.00 203,327.12				
Artificial Turf / Rub	Stripping and Signage   32-1700 Artificial Turf / Bubberized Play Surface   32-1800	32-1700		LS			3,500.00			3,500.00				paprived
	Fencing 32-3100	32-1000		rs		,					1			Excluded None
	Retaining Wall	32-9000	-	rs		26,880.00	1			•	1	•		Carried in Landscaping
	Subtotal DIV 32	CCT						256,398.12		238,478.12				
33 UTLITIES	Utilities 33-0000	33-0000	-	rs		142,500.00	254,240.00		254,240.00	i	,	1	,	
	Subtotal DIV 33	ССТ						254,240.00	254,240.00					
				T O	TOTAL ALL DIVISIONS	6,528,867.99		7,231,308.44	5,463,176.80	1,015,966.50	623,280.31	113,283.98	15,600.86	
BUILDING PERMIT & FEES	Building Permit Plan Check Fire Dept Use Tax	No No		23 23 23 24 25 25 25										Building Permit and Fees by Owner ADM to assist in permit submittal process.
					Total Permits									
									Breakout 1	Breakout 2	Breakout 3	Breakout 4	Breakout 5	
		C	ONSTRU	UCTION	CONSTRUCTION SUBTOTAL	6,528,867.99		7,231,308.44	5,463,176.80	1,015,966.50	623,280.31	113,283.98	15,600.86	
		,	ADM	ADM Profit:	4.00%	261,154.72		289,252.34	218,527.07	40,638.66	24,931.21	4,531.36	624.03	
		ADM L	Builder's Kisk ins ADM Liability Insurance	surance	0.23%	78,346.42		16,078.27	65,558.12	2,339.92 12,191.60	7,479.36	1,359.41	187.21	
		CC	NSTRUC	CTION	CONSTRUCTION BASE PRICE	6,884,691.29	7,625,414.75	7,625,414.75	5,760,919.93	1,071,336.67	657,249.09	119,457.96	16,451.11	
			Bor	Bond Fee	1.00%	68,846.91		76,254.15	57,609.20	10,713.37	6,572.49	1,194.58	164.51	
		Estima	Contingency Estimating Contingency	Contingency Contingency	3.50%	240,964.20 214,540.74		266,889.52 228,762.44	201,632.20 172,827.60	37,496.78 32,140.10	23,003.72	4,181.03 3,583.74	575.79 493.53	
	CONSTRUCTION BASE PRICE + CONTINGENCY	TON BA	SE PRICE	E + CO!	NTINGENCY	7,409,043.14	8,197,320.86	8,197,320.86	6,192,988.93	1,151,686.92	706,542.77	128,417.30	17,684.94	